



SURI VIDYASAGAR COLLEGE

SURI, BIRBHUM, 731101.

(Govt. Sponsored)

Established : 1942

ACCREDITED BY NAAC (2nd Cycle)-B⁺⁺

Affiliated to the University of Burdwan & Recognized under UGC 2(f)/12B

B. A., B. Sc. & B. Com. (Hons. & General) & M. Sc. in Zoology

Institution is Ragging Free

Ref. Memo No.-SVC/ 348/2024

Dated: 23.08.2024

NOTICE INVITING QUOTATION

Sealed Quotations are invited for Civil Works mentioned below Maintained as Per PWD Specification Schedule from the Person with credentials and GST Entitled within 7 days of publication of Notice.

Name Of The Work – Floor Lifting in Chemistry Department at Room-3 in Suri Vidyasagar College

Schedule Of The Work :-

(Schedule Followed: PWD SOR Vol-I w. e. f. 1.11.2017)

Sl No.	Description of Item	Unit	No	Length (m)	Breadth (m)	Height (m)	Quantity	Total Quantity
1	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	Cum	1	6.000	9.000	0.425	22.950	22.950
	By Fine sand							
	<u>GROUND FLOOR</u>							
2	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	Sqm	1	6.000	9.000	-	54.000	54.000
	<u>GROUND FLOOR</u>							
3	Cement concrete with graded stone ballast (40 mm size excluding shuttering) In ground floor (A) [Pakur Variety]	Cum	1	6.000	9.000	0.075	4.050	4.050
	b) 1:3:6 proportion							
4	Artificial stone in floor, dado, staircase etc. with cement concrete with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust inproportion (2:1) (II) 25mm thick. In ground floor.	Sqm	1	6.000	9.000	-	54.000	54.000
	<u>GROUND FLOOR</u>							

J.K. Panichha
Principal 23/08/2024

Suri Vidyasagar College

Principal

Suri Vidyasagar College
Suri, Birbhum, 731101

Email:surividyasagarcollege1942@gmail.com

Phone:03462 251754